

INTACH

Tender Notice

No. 10/136/Main./2016-17

04.01.2017

Sealed quotations are invited for supply of domestic Hi-Wall Split unit to be installed in the INTACH Documentation Centre in the basement of INTACH, 71, Lodhi Estate, New Delhi-110003 as per the detail given below:

S.No.	Description	Quantity
1.	Supply of 5 Star Rating 2.0 TR Hi-Wall Split (Wall mounted) type Air-conditioner with rotary compressor	2
2.	Supply of 3.0 TR Cassette Type Air-Conditioner with Energy Efficient Scroll Compressors	2

2. The technical specifications are given in Annexure I and Annexure II. Vendor may see the installation plan at the INTACH basement where the unit to be installed.

3. All the reputed vendors should send their sealed quotations to Director (Admin), INTACH at 71, Lodi Estate, New Delhi on or before by 18th January, 2017 by 2:00 p.m. Quotations will be opened at 4:00 p.m. on the same day. INTACH has the absolute right to reject the quotations without assigning any reason.

Director (Admin)
INTACH

Upgradation Of Library Basement					
Technical Specification					
INTACH , 71, LODHI ESTATE, New Delhi - 110003					
SUPPLY/INSTALLATION/TESTING/COMMISSIONING OF 3.0 TR CASSETTE UNITS					
S.no	Description	Quantity	Unit	Unit Rate	Amount
1	Supply of 3.0 TR Cassette Type Airconditioner with Energy Efficient Scroll Compressors.	2	Nos.		
Total Basic Amount					
VAT @12.5%					
Total with Taxes					
2	Shifting, Lifting, Installation, Testing and commissioning of Cassette / Mega Split unit with pressure Testing, Vaccumising & Refrigerant Charging.				
a	Capacity 3.0 TR (Cassette Type AC)	2	Nos.		
3	Providing & Installation of Suitable size Refrigerant piping with insulation.				
a	For 3.0 TR Cassette Unit.		RM		
4	Providing & Installation of Suitable size control cable from Indoor to Outdoor unit.				
a	For 3.0 TR Cassette AC 65		RM		
5	Providing & Installation of hard PVC Drain Pipe.				
a	25 mm Dia.		RM		
b	32 mm Dia.		RM		
6	Providing & Installation of MS choki type frame for Condensing units				
a	For 3.0 TR Cassette Split unit.	2	No.		
7	Power Cable From MCB upto Outdoor unit. (Copper Armoured)				
a	For 3.0 TR Unit.		RM		
8	Providing & Fixing of suitable rating weather proof MCB with box				
			No.		
9	Providing & Installation of GI Cable tray without cover of 200 mm wide.				
			RM		
Total Basic Amount					
Service Tax @15.0%					
Total with Taxes					
Grand Total					

Upgradation Of Library Basement					
Technical Specification					
INTACH , 71, LODHI ESTATE, New Delhi - 110003					
SUPPLY/INSTALLATION/TESTING/COMMISSIONING OF 2.0 TR HI-WALL UNITS.					
S.no	Description	Quantity	Unit	Unit Rate	Amount
1	Supply of 5 Star Rating 2.0 TR Hi-Wall Split (Wall mounted) type Airconditioner with rotary Compressors.	2	No.		
Total Basic Amount					
VAT @12.5%					
Total with Taxes					
2	Shifting, Lifting, Installation, Testing and commissioning of Mega Split unit with pressure Testing, Vaccumising & Refrigerant Charging.				
a	Capacity 2.0 TR	2	No.		
3	Providing & Installation of Suitable size Refrigerant piping with insulation.				
a	For 2.0 TR Hi-Wall Split Unit.		RM		
4	Providing & Installation of Suitable size control cable from Indoor to Outdoor unit.				
a	For 2.0 TR Hi-Wall Split AC		RM		
5	Providing & Installation of hard PVC Drain Pipe.				
a	25 mm Dia		RM		
6	Providing & Installation of MS choki type frame for Condensing units.				
a	For 2.0 TR Hi-Wall Split unit		No.		
7	Power Cable From MCB upto Outdoor unit. (Copper Armoured)				
a	For 2.0 TR Hi-Wall Split unit		RM		
8	Providing & Fixing of suitable rating weather proof MCB with box.		No.		
Total Basic Amount					
Service Tax @15.0%					
Total with Taxes					
Grand Total					